

March 12, 2001

Mr. Chuck Schwer Agency of Natural Resources Department of Environmental Conservation 103 S. Main St./West Office Waterbury, VT 05671-0404

RE: Summary Report of Subsurface Petroleum Contamination at the former St.

Johnsbury House, St. Johnsbury, Vermont.

VT-DEC #2000-2803

Dear Mr. Schwer,

The following report is a copy of the Summary Report of Subsurface Petroleum Contamination at the former St. Johnsbury House, St. Johnsbury, Vermont.

Please call with any questions or concerns.

Sincerely,

Rob Danckert Project Manager

C: File: 100041751

Enc.

### SUMMARY REPORT OF SUBSURFACE PETROLEUM CONTAMINATION AT THE FORMER ST. JOHNSBURY HOUSE ST. JOHNSBURY, VERMONT

**FEBRUARY 6, 2001** 

Site Location:

FORMER ST. JOHNSBURY HOUSE 44 MAIN STREET ST. JOHNSBURY, VERMONT

> GI Project #100041751 VTDEC SITE #00-2803

> > Prepared For:

Mr. Chris Boffa
Pinnacle Builders, Inc.
7 Aspen Dr.
S. Burlington, Vermont 05403-6247

Prepared By:





E.

#### **Table of Contents**

I.	INTRODU	ICTION1
n.	INVESTIC	GATIVE PROCEDURES1
A. B. C. D.	DETERM GROUNI SENSITI	IG METHODS AND MONITORING WELL INSTALLATION
III.	CONCLU	SIONS 4
IV.	RECOMM	IENDATIONS 5
APF	PENDICE:	MAPS 1) Site Location Map 2) Site Map 3) Groundwater Contour Map
	B.	BORING LOGS
	C.	LIQUID LEVEL MEASUREMENT DATA
	D.	GROUNDWATER QUALITY SUMMARY DATA

GROUNDWATER LABORATORY ANALYTICAL DATA

#### I. INTRODUCTION

This report summarizes the results of the preliminary investigation of subsurface petroleum contamination at the former St. Johnsbury House at 44 Main St., St. Johnsbury, Vermont. (see Site Location Map in Appendix A). This work was conducted by Griffin International, Inc. (Griffin) for Mr. Chris Boffa of Pinnacle Builders, Inc. Investigative efforts at the site were initially conducted due to the detection of subsurface petroleum contamination during the removal of one 1,000-gallon #2 fuel oil underground storage tank (UST), one 2,000 gallon fuel oil UST, and one 3,000 gallon fuel oil UST in August 2000. The 1,000 gallon #2 fuel oil UST was the only tank that exhibited signs of contamination. This investigative effort is the result of a request made by Mr. Chuck Schwer of the Vermont Department of Environmental Conservation (VTDEC) in a September 14, 2000 letter to Griffin International. Scheduled work was approved by Mr. Schwer in a December 6, 2000 letter to Griffin.

Scheduled work for this site investigation included the drilling of four monitoring wells, the collection and laboratory analysis of groundwater samples from the four monitoring wells (MW-1 through MW-4) that are located in the vicinity of the former #2 fuel oil UST. Work has been conducted in accordance with Griffin's Revised Work Plan and Cost Estimate for an Initial Subsurface Investigation dated December 5, 2000.

#### II. INVESTIGATIVE PROCEDURES

### A. Drilling Methods and Monitoring Well Installation

On January 8 and January 9, 2000, four (4) soil borings were advanced by T&K Drilling of East Swanzea, New Hampshire using a truck-mounted, 4.25" inside diameter (ID), hollow-stem auger drill rig. Monitoring wells MW-1, MW-2, MW-3, and MW-4 were constructed in the four soil borings that were installed in the vicinity of the former #2 fuel oil UST. Monitoring wells MW-3 was installed in a location believed to be crossgradient of the former UST area. Monitoring well MW-4 was installed in a location believed to be downgradient of the former UST area. Monitoring well MW-2 was installed in an area believed to be adjacent to the source area while MW-1 was installed in a location believed to be upgradient of the source area. The monitoring wells were installed to help define the degree and extent of potential petroleum contamination in the vicinity of the former UST (see Site Map, Appendix A).

Soil samples were collected at 5-foot intervals in each boring using a two-foot long, 2" ID stainless steel split-spoon sampler. The split-spoon sampler was decontaminated in the field with a solution of Alconox (detergent) and water to prevent potential cross-contamination. Soil samples were screened for VOCs using an Hnu<sup>TM</sup> Model HW-101 Photoionization Detector (PID) equipped with a 10.2 eV bulb. Soils were screened using the Griffin Jar/Polyethylene Bag Headspace Screening Protocol, which conforms to state and industry standards. In addition, soil characteristics were recorded in boring logs by the Griffin drilling supervisor (see Boring Logs, Appendix B).

All of the monitoring wells are constructed of newly threaded, flush-joint, schedule 40, 2" ID polyvinyl chloride (PVC) riser attached to a 0.010-slot, 2" ID PVC screen. The screen is attached to the riser by a watertight, threaded, flush joint coupling. A sealed watertight roadway box was installed at grade to protect the well. The top of the riser is capped with a lockable expansion plug.

The screened interval in wells MW-1 through MW-4 ranges from 20 to 30-feet below surface grade (bsg). A silica sand pack was placed around the screened portion of each well in order to prevent fine sediments within the groundwater from entering the well. A bentonite seal was placed in the annulus immediately above the sand pack to prevent infiltration into the borehole. An additional seal was placed closer to the ground surface to prevent surface water from entering the borehole. Please refer to the Boring Logs in Appendix B for further details on the construction of each well.

#### SB-1/MW-1

Subsurface conditions encountered from zero to approximately 2.0 and 25 to 27 feet below surface grade (bsg) in boring SB-1 consisted of moist, dark brown, sandy lean clay. Soils encountered at 5 to 7 feet bsg consisted of poorly graded sand with gravel. Soils encountered at 10 to 12, 15-17, 20 to 22, and 30 to 32 feet bsg consisted of light brown, silty sand. Driller refusal was not encountered throughout drilling of MW-1. VOCs were not recorded above the detection limits of the PID in the screened soils during the advancement of this boring. Groundwater was encountered at approximately 26.1 feet bsg.

#### SB-2/MW-2

Subsurface conditions encountered from zero to approximately 2, 4 to 6, 9 to 11, 14 to 16, and 19 to 21 feet below surface grade (bsg) in boring SB-2 consisted of moist, poorly graded, brown silty sand. From 24 to 26 feet bsg a poorly graded sand with silt was encountered. Poorly graded sand was encountered at 29 to 31 feet bsg. Driller refusal was not encountered at SB-2. VOCs were detected from approximately 4 to 26 feet bsg ranging from 0.8 to 12.8 parts per million (ppm). Groundwater was encountered at approximately 25.8 feet bsg. Contaminated soils were stockpiled at the north side of the St. Johnsbury House over a plastic sheet.

#### SB-3/MW-3

Subsurface conditions encountered from zero to approximately 2, 5 to 7, and 10 to 12 feet bsg in the boring for monitoring well MW-3 consisted of well graded sand with silt. The boring for MW-3 was advanced to 32 feet below surface grade (bsg). Soil encountered at 15 to 17, 20 to 22, 25 to 27, and 30 to 32 feet bsg consisted of light grey and dark brown poorly graded sands. Driller refusal was not encountered throughout drilling of SB-3. VOCs were not recorded above

the detection limits of the PID in the screened soils during the advancement of this boring. Groundwater was encountered at approximately 26 to 27 feet bsg.

#### SB-4/MW-4

Subsurface conditions encountered from zero to approximately 2.0 and 15 to 17 feet bsg in the boring for monitoring well MW-4 consisted of silty sand. The boring for MW-4 was advanced to 32 feet below grade. Soils encountered at 5 to 7, 10 to 12, 20 to 22, 25 to 27, and 30 to 32 feet bsg consisted of poorly graded sand with silt. Driller refusal was not met throughout drilling of this boring. VOCs were not recorded above the detection limits of the PID during the advancement of this boring. Groundwater was encountered at approximately 25 to 27 feet bsg.

### B. Determination of Groundwater Elevations, Flow Direction, and Gradient

On January 19, 2001, depth to water measurements were taken with the use of an interface probe in the four monitoring wells. The relative water table elevation was determined, based on an arbitrary benchmark of 100 feet (top of casing for MW-1).

As displayed on the groundwater contour map included in Appendix A, the groundwater flow direction for the January 19, 2001 sampling round was estimated to be in a northwesterly direction at a gradient of approximately 0.8%. No free phase petroleum product was observed in any of the monitoring wells on January 19, 2001. Groundwater level data are recorded in Appendix C.

#### C. Groundwater Sample Collection and Analysis

On January 19, 2001 groundwater samples were collected from the four monitoring wells. The samples were stored on ice, and submitted to Endyne, Inc. of Williston, Vermont, under proper chain-of-custody procedures. The samples were collected according to Griffin's groundwater sampling protocol, which complies with industry and state standards. The samples were analyzed for VOCs by EPA Method 8021B and for Total Petroleum Hydrocarbons via EPA Method 8015 DRO. In accordance with VTDEC protocols and for quality assurance/quality control (QA/QC) purposes, a duplicate sample (MW-1) was also collected and analyzed for VOCs by EPA Method 8021B and 8015 DRO.

No VOCs were reported as detected above laboratory detection limits in groundwater from monitoring wells MW-1, MW-2, MW-3, and MW-4 (See Appendix D).

Results from the analyses of the duplicate sample indicate that adequate QA/QC measures were maintained during sample collection and analysis.

#### D. Sensitive Receptor Risk Assessment

A sensitive receptor risk assessment was conducted at the site during the sampling event conducted on January 19, 2001 and after the results of the lab analyses were reviewed.

The former St. Johnsbury House and other buildings in the area are considered at minimal risk from the on-site petroleum contamination due to the low concentrations of contamination detected at the site, and given the other residential distances from the source area. Indoor air inside of rooms adjacent to the UST excavation were screened with a PID on August 10, 2000. No elevated readings were recorded.

The nearest surface water is the Passumpsic River, located approximately 700 yards east of the source area at the St. Johnsbury House and the Sleepers River that is located approximately 650 yards west of the St. Johnsbury House. The Sleepers River is downgradient of the source area based upon the January 19, 2001 water table elevations. The Sleepers River is considered at minimal risk of petroleum impact from the former St. Johnsbury House given its distance from the subject site and the low concentrations of petroleum constituents detected in soils beneath the site.

#### III. CONCLUSIONS

Based on the additional site investigation at the St. Johnsbury House site, the following conclusions are offered:

- One 1,000-gallon #2 fuel oil UST was removed from the former St. Johnsbury House site on August 10, 2000. Peak PID readings measured during this excavation measured 226 ppm. Four groundwater monitoring wells were installed at the subject site in order to further characterize the degree and extent of residual petroleum impacts at the site on January 8 and January 9, 2001. PID readings in soil ranged from non-detect to 12.8 ppm on the two days of drilling.
- 2. The groundwater flow direction for the January 19, 2000 sampling round was estimated to be in a northwesterly direction at a gradient of approximately 0.8%.
- 3. No free phase petroleum product was observed in any of the monitoring wells on the January 19, 2000 sampling round.
- 4. No VOCs were reported as detected above laboratory detection limits in groundwater from monitoring wells MW-1, MW-2, MW-3, or MW-4.
- 5. Based on field observations and analytical results, residual petroleum impacts are present to a limited extent in soil at the location of the former St Johnsbury House, chiefly in the vicinity of monitoring well MW-2, which is located adjacent to the former UST pit. There are

currently no other known receptors affected by subsurface petroleum contamination from the former #2 fuel oil UST at the former St. Johnsbury House property.

#### IV. RECOMMENDATIONS

Based on the results of this site investigation, Griffin recommends that the former St. Johnsbury House in St. Johnsbury, Vermont be considered for closure and be removed from the VTDEC Active Hazardous Waste Sites List. This recommendation is offered based upon achievement of the following closure criteria, as per the VTDEC Site Management Activity Completed (SMAC) Checklist (dated December 1, 1997):

1) The source(s), nature, and extent of the petroleum contamination at the site have been adequately defined.

See Conclusions #1, #2, #3, #4, and #5.

2) Source(s) has been removed, remediated, or adequately contained.

See Conclusions #1 #4, and #5.

3) Levels of contaminants in soil and groundwater shall be stable, falling, or non-detectable.

See Conclusions #4.

4) Groundwater enforcement standards are met at the following compliance points:

Any point of present use of groundwater as a source of potable water: Potable water for the former St. Johnsbury House is supplied from town water. Also, see Conclusion #4.

Any point at or within the boundary of any Class I groundwater area: The former St. Johnsbury House is not within a Class I groundwater area.

Any point at the boundary of the property on which the contaminant source is located: See Conclusion #4.

5) Soil guideline levels are met. If not, engineering or institutional controls are in place.

See Conclusion #1. Also, the area in the vicinity of the former UST location is paved. However, impacted soils were detected only in the boring for monitoring well MW-2 at a depth of 4-6 feet bsg. This 0-4 feet bsg "buffer" of non-impacted soils would likely inhibit exposure via dermal contact to petroleum-impacted soils.

6) No unacceptable threat to human health or the environment exists on site.

See Conclusions #4 and #5.

7) Site meets RCRA requirements.

Available records indicate that the former St. Johnsbury House is not in violation of the Resource Conservation and Recovery Act (RCRA) as defined in 40 CFR 264.

8) Site meets CERCLA requirements.


Available records indicate that the former St. Johnsbury House is not in violation of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) as defined in 40 CFR 300.


Additionally, Griffin recommends that the four site monitoring wells be properly abandoned according to VTDEC requirements for well closure.


#### APPENDIX A

#### MAPS

1) SITE LOCATION MAP 2) SITE MAP 3) GROUNDWATER CONTOUR MAP







APPENDIX B
BORING LOGS

## BORING LOG AND WELL CONSTRUCTION DIAGRAM

Well No: MW-1

#### ST. JOHNSBURY HOUSE

CT	JOHNSBURY.	VERMONT	
51.	JUMNSBURT.	VERIVION	

Project #100041751

Griffin Project #	100041751	Date	Installed:	1/8/01-1/9/01	П	_
Grinin Project #	Griffin Internationa		g Method:	Hollow-stem auger		
	T&K Drilling		Diameter.:	4.25"	l_	8
Supervised by:	•	Developmen		Bailing	夏	Ž
Logged by:			ed Length:	10 Ft.	ڴۣٳ	္သ
	Vell Construction	Pen/Rec (")	Interval (')	Soil Characteristics	Letter Symbol	Graphic Symbol
Grade = 0	00, 000,000,000	Blow Count		Dirt surface		
1.0		CUTTINGS	<del></del>	Dark brown, sandy lean clay	CL	
2.0		NA	ND		1	
3.0 Ft <gra< td=""><td>te M</td><td></td><td></td><td></td><td>l</td><td></td></gra<>	te M				l	
4.0					1	
5.0	77 · · · · · · · · · · · · · · · · · ·	24/17	5-7'	Light brown, poorly graded sand w/ gravel.	SP	<b>////</b>
6.0		4-3-4-4	0.2		ł	
7.0					]	
8.0					]	ŀ
9.0						
10.0		24/20	10-12'	Light brown, silty sand.	SM	
11.0		3-3-4-4	ND			
12.0						
13.0						
14.0						
15.0		24/18	15-17'	Light brown, silty sand.	SM	
16.0		3-5-5-4	ND			
17.0						
18.0						
19.0						
20.0		24/21	20-22'	Light brown, silty sand.		L
21.0		4-4-6-5	ND	Trace amounts of gravel present. Iron staining visible.	SM	M
22.0						
23.0	26.1					
- 24.0						
25.0		24/19	25-27'	Dark brown, sandy lean clay.	CL	
26.0	73.00	5-5-3-8	ND		]	
27.0						1
28.0	1/19/01				ļ.	
29.0		24/20	30-32'	Dark brown, silty sand	SM	
30.0		3-5-6-6	ND			
31.0	(\$100 ALCON)					
32.0				Base of Exploration.		
33.0						
	<del></del>					

Road Box with Bolt Down Cover, Set in Cement. Existing Surface. Bentonite Seal Placed in Annulus. Grade #1 Silica Sand Pack Placed in Annulus.

Drill Cuttings Placed in Annulus.

ND - Non-Detect NA - Not Applicable UNK-Unknown

Locking Plug.

2.0" ID, Schedule 40 PVC Riser.

2.0" ID, Schedule 40 PVC, 0.010"-Slotted Well Screen

Plug Point

Approximate Water Level During Drilling (feet below surface grade)

Static Water Level (feet)

## BORING LOG AND WELL CONSTRUCTION DIAGRAM

Well No: MW-2

#### ST. JOHNSBURY HOUSE

Project #100041751 ST. JOHNSBURY, VERMONT Griffin Project #: 100041751 1/8/01-1/9/01 Date Installed: Hollow-stem auger Drilled by: Griffin International Drilling Method: 4.25" Graphic Symbol Driller: T&K Drilling Boring Diameter.: Letter Symbol Development Method: Bailing Supervised by: RD Screened Length: 10 Ft. Logged by: RD **Soil Characteristics** Pen/Rec (") Interval (") **Well Construction** Blow Count PID (ppm) Dirt surface Grade = 0 sм 🖁 Dark brown, silty sand. CUTTINGS NΑ ND 3.0 Ft<Grade SM Dark brown, silty sand. 24/27 4-6 4.0 12.8 4-4-5-5 5.0 6.0 7.0 8.0 Light brown, silty sand. 24/22 9-11 9.0 3-3-4-4 4.5 10.0 11.0 12.0

SM 13.0 **SM** 14-16' Light brown, silty sand. 24/18 14.0 0.2 Gradational contact to light grey, silty sand 4-5-7-8 15.0 16.0 17.0 18.0 SM 24/19 19-21' Light brown, silty sand. 19.0 4-6-7-8 3.4 20.0 21.0 25.8 23.0 SP-Poorly graded sand with silt. 24/22 24-26' 24.0 SM 0.8 73.17 6-6-7-5 25.0  $\forall$ 26.0 SP 🔆 29-31 Poorly graded sand. 1/19/01 24/23 27.0 ND 1-1-2-5 28.0 Base of Exploration. 29.0 30.6 31.0 32.0 33.0 34.0 Legend

Road Box with Bolt Down Cover, Set in Cement. Existing Surface. Bentonite Seal Placed in Annulus.

Grade #1 Silica Sand Pack Placed in Annulus.

Drill Cuttings Placed in Annulus.

NO - Non-Detect NA - Not Applicable **UNK-Unknown** 

Locking Plug.

2.0" ID, Schedule 40 PVC Riser.

2.0" ID, Schedule 40 PVC, 0.010"-Slotted Well Screen

Plug Point

Approximate Water Level During Drilling (feet below surface grade)

Static Water Level (feet)

## BORING LOG AND WELL CONSTRUCTION DIAGRAM Well No: MW-3

#### ST. JOHNSBURY HOUSE

ST. JOHNSBURY, VERMONT Project #100041751

OD41751 URIFF

虿

Griffin Project #: 100041751 Date Installed: 1/8/01-1/9/01

Drilled by: Griffin International Drilling Method: Hollow-stem auger

Boring Diameter.: 4.25"

Supervised by: RD Development Method: Balling Logged by: RD Screened Length: 10 Ft.	IΕ	
Logged by: RD Screened Length: 10 Ft.	&	S)
Well Construction Pen/Rec (") Interval (") Soil Characteristics	Letter Symbol	Graphic Symb
Grade = 0 Blow Count PID (ppm) Asphalt surface		
1.0 CUTTINGS 1-2' Dark brown, well graded sand with silt.	SW-	M.
2.0 NA ND	SM	
3.0 Ft <grade< td=""><td></td><td>1</td></grade<>		1
4.0		ļ.,,,,
5.0 24/20 5-7' Light brown, well graded sand with slit.	SW-	Mi.
8.0 2-3-4-6 ND	SM	1
7.0		1
8.0		1
9.0		1
10.0 24/23 10-12' Light brown, silty sand.	SM	
11.0 3-4-6-7 ND		
12.0		Į.
13.0		İ
14.0		
15.0 24/19 15-17' Light grey, poorly graded sand.	SP	<b> </b>
16.0 5-6-9-12 ND		` `
17.0	ĺ	
18.0		
19.0	]	
20.0 24/21 20-22 Light grey, poorly graded sand.		
1 204	SP	<b>***</b>
		'''
23.0	- 1	
24.0 25.0 73.47 24/21 25-27' Dark brown, poorly graded sand.	SP	<b></b>
L 2304		
28.0 29.0 24/23 30-32 Dark brown, poorly graded sand.	SP	<b>////</b>
	į.	1
TOTAL		1
Base of Exploration.		
32.0		1
33.0		
34.0		
35.0	1	
36.0		
37.0		
38.0		Щ,

Road Box with Bolt Down Cover, Set in Cement.

Existing Surface.

Bentonite Seal Placed in Annulus.

Orill Cuttings Placed in Annulus.

ND - Non-Detect

NA - Not Applicable UNK-Unkown Locking Plug.

2.0" ID, Schedule 40 PVC Riser.

2.0" ID, Schedule 40 PVC, 0.010"-Slotted Well Screen

Plug Point

Approximate Water Level During Drilling (feet below surface grade)

Static Water Level (feet)

## BORING LOG AND WELL CONSTRUCTION DIAGRAM

Well No: MW-4

#### ST. JOHNSBURY HOUSE

ST. JOHNSBURY, VERMONT Project #100041751

GRIFFIN

	UKT, VENIVION	Date	Installed:	1/8/01-1/9/01		
Griffin Project #	r: 100041751 : Griffin Internationa		g Method:	Hollow-stem auger		
Onlied by Oriller			Diameter.:	4.25"		ō
Supervised by	_	Developmer		Bailing	뎙	탩
Logged by			ed Length:	10 Ft.	<u>\$</u>	ŝ
	Vell Construction	Pen/Rec (")	Interval (')	Soil Characteristics	Letter Symbol	Graphic Symbol
Grade = 0		Blow Count	PID (ppm)	Dirt surface		_
1 12222	Zimminim XXXX	CUTTINGS		Silty sand	SM	
2.0	<b>∞</b>	NA	ND			300
3.0 Ft <gra< td=""><td>de (4)</td><td>  "</td><td> </td><td></td><td></td><td>ŀ</td></gra<>	de (4)	"				ŀ
4.0		Į		'		
5.0	M Company	24/23	5-7'	Poorly graded sand with silt.	SP.	· <i>VIII</i>
6.0		4-4-4-4	ND		SM	
-1		' ' ' '				
7.0						i i
8.0						
9.0		04/04	10-12'	Poorly graded sand with silt.	SP.	. ////
10.0		24/21		Sharp sitt contact at 12'.	SM	Viri.
11.0		4-5-5-6	ND	Sharp sin contact at 12.	-	1
12.0						
13.0					l	1
14.0				Links harry atthe agend	l sm	13434
15.0		24/22	15-17'	Light brown, silty sand.	3141	
16.0		5-5-6-6	ND			-
17.0	<b>22</b>					
18.0					1	
19.0						11111
20.0	25-27	24/21	20-22'	Poorly graded sand with silt.	SP	
21.0		5-6-7-9	ND	2" silt layer @ 20'.	SM	
22.0		<u> </u>	İ			
23.0	73.75		1			
24.0						1,,,,
25.0	1/19/01	24/20	25-27'	Poorly graded sand with silt.	SP	1111
26.0		1-3-3-2	ND		SM	! <b> </b>
27.0					1	
- 1		1				l
28.0		24/19	30-32	Poorly graded sand with silt.	SP	- ////
29.0		1-1-5-5	ND		Sīv	۱ [ ```
30.0	EANS TANK		""	}		
31.0 32.0		1		Base of Exploration.		
-	<del></del>	+				1
33.0 34.0						
34.0			<u> </u>	Legend		
Road	Box with Bolt Down Cover,	Set in Cement		Locking Plug.		

Existing Surface.

Bentonite Seal Placed in Annulus.

Grade #1 Silica Sand Pack Placed in Annulus.

Drill Cuttings Placed in Annulus.

ND - Non-Detect

NA - Not Applicable

UNK- Unknown

2.0" ID, Schedule 40 PVC Riser.

2.0" ID, Schedule 40 PVC, 0.010"-Slotted Well Screen

Plug Point

Approximate Water Level During Drilling (feet below surface grade)

Static Water Level (feet)

# APPENDIX C LIQUID LEVEL MEASUREMENT DATA

#### **Groundwater Table Elevations**

Well I.D.	Well Depth	Top of Casing Elevation	Depth to Product	Depth to Water	Corrected Water Table Elevation
MW-1	30.0	100.00	<b>.</b>	27.00	73.00
MW-2	29.0	99.10	-	25.93	73.17
MW-3	30.0	99.18	-	25.71	73.47
MW-4	30.0	97.36	<del>-</del>	23.61	73.75

All values registered in feet.

Elevations are based on an Arbitrary Datum - MW-1 set at 100.00 feet.

NS-Not sampled

# APPENDIX D GROUNDWATER QUALITY SUMMARY DATA

#### **GROUNDWATER QUALITY SUMMARY**

#### MW-1

	·····	
Sample Date:	1/19/01	2000
Analytical Method:	8021B	VGES
PARAMETER		(ppb)
Benzene	ND>1.0	5.
Toluene	ND > 1.0	1,000.
Ethylbenzene	ND>1.0	700.
Xylenes	ND > 1.0	10,000.
Total BTEX	ND>1.0	-
MTBE	ND > 10.0	40.
1,3,5-Trimethylbenzene	ND>1.0	4.
1,2,4-Trimethylbenzene	ND>1.0	5.
Naphthalene	ND>1.0	20.
Total Targeted VOCs	ND	-

#### MW-2

Sample Date:	11/27/00	2000
Analytical Method:	8021B	VGES
PARAMETER		(ppb)
Benzene	ND > 1.0	5.
Toluene	ND>1.0	1,000.
Ethylbenzene	ND>1.0	700.
Xylenes	ND>1.0	10,000.
Total BTEX	ND>1.0	_
MTBE	ND>10.0	40.
1,3,5-Trimethylbenzene	ND>1.0	4.
1,2,4-Trimethylbenzene	ND>1.0	5.
Naphthalene	ND>1.0	20.
Total Targeted VOCs	ND	

All Values Reported in ug/L (ppb)

ND - None detected above sample specific detection limit

Bold indicates a detection. Concentrations which are equal to or greater than the VGES are shaded.

VGES - Vermont Groundwater Enforcement Standard (Groundwater Protection Rule and Strategy, January 20, 2000)

#### MW-3

Sample Date:	1/19/01	2000
Analytical Method:	8021B	VGES
PARAMETER		(ppb)
Benzene	ND>1.0	5.
Toluene	ND>1.0	1,000.
Ethylbenzene	ND>1.0	700.
Xylenes	ND>1.0	10,000.
Total BTEX	ND>1.0	_
MTBE	ND>10.0	40.
1,3,5-Trimethylbenzene	ND > 1.0	4.
1,2,4-Trimethylbenzene	ND > 1.0	5.
Naphthalene	ND>1.0	20.
Total Targeted VOCs	ND	_

#### MW-4

Sample Date:	1/19/01	2000
Analytical Method:	8021B	VĢES
PARAMETER		(ppb)
Benzene	ND > 1.0	5.
Toluene	ND > 1.0	1,000.
Ethylbenzene	ND>1.0	700.
Xylenes	ND>1.0	10,000.
Total BTEX	ND>1.0	
MTBE	ND>10.0	40.
1,3,5-Trimethylbenzene	ND>1.0	4.
1,2,4-Trimethylbenzene	ND>1.0	5.
Naphthalene	ND>1.0	20.
Total Targeted VOCs	ND	•

All Values Reported in ug/L (ppb)

ND - None detected above sample specific detection limit

Bold indicates a detection. Concentrations which are equal to or greater than the VGES are shaded.

VGES - Vermont Groundwater Enforcement Standard (Groundwater Protection Rule and Strategy, January 20, 2000)

#### MW-1

Sample Date:	1/19/01
Analytical Method:	8015 DRO
PARAMETER	
Total Petroleum Hydrocrbns.	ND> 0.40

#### MW-2

Sample Date:	1/19/01
Analytical Method:	8015 DRO
PARAMETER	
Total Petroleum Hydrocrbns.	ND> 0.40

#### MW-3

Sample Date:	
Analytical Method:	8015 DRO
PARAMETER	
Total Petroleum Hydrocrbns.	ND> 0.40

#### MW-4

Sample Date:	
Analytical Method:	8015 DRO
PARAMETER	
Total Petroleum Hydrocrbns.	ND> 0.40

All Values Reported in mg/L (ppm)

ND - None detected above sample specific detection limit

Bold indicates a detection. Concentrations which are equal to or greater than the VGES are shaded.

VGES - Vermont Groundwater Enforcement Standard (Groundwater Protection Rule and Strategy, January 20, 2000)

# APPENDIX E GROUNDWATER LABORATORY ANALYTICAL REPORT



#### LABORATORY REPORT

**Laboratory Services** 

160 James Brown Drive Williston, Vermont 05495 (802) 879-4333` FAX 879-7103

Griffin International

PO Box 943

Williston, VT 05495

Attn:

PROJECT: Former St. Johns House/#1000417

ORDER ID: 11029

RECEIVE DATE: January 19, 2001

REPORT DATE: February 8, 2001

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody. Different groups of analyses may be reported under separate cover.

All samples were prepared and analyzed by requirements outlined in the referenced methods and within the specified holding times.

All instrumentation was calibrated with the appropriate frequency and verified by the requirements outlined in the referenced methods.

Blank contamination was not observed at levels affecting the analytical results.

MUM

Analytical method precision and accuracy was monitored by laboratory control standards which include matrix spike, duplicate and quality control analyses. These standards were determined to be within established laboratory method acceptance limits, unless otherwise noted.

Reviewed by,

Harry B. Locker, Ph.D. Laboratory Director

enclosures



#### **Laboratory Services**

160 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

#### LABORATORY REPORT

CLIENT: Griffin International

PROJECT: Former St. Johns House/#100041751

REPORT DATE: February 8, 2001

ORDER ID: 11029

DATE RECEIVED: January 19, 2001

SAMPLER: RD ANALYST: 128

Ref. Number: 168256	Site: Duplicate	·	Date Sampled: January 19, 200	1 Time: 12:04 PM
Parameter Parameter	Result	<u>Unit</u>	<u>Method</u>	Analysis Date
TPH 8015 DRO	< 0.40	mg/L	SW 8015B	2/7/01
Ref. Number: 168257	Site: MW-1		Date Sampled: January 19, 200	1 Time: 12:27 PM
<u>Parameter</u>	Result	<u>Unit</u>	Method	Analysis Date
TPH 8015 DRO	< 0.40	mg/L	SW 8015B	2/2/01
Ref. Number: 168258	Site: MW-2		Date Sampled: January 19, 200	1 Time: 12:46 PM
<u>Parameter</u>	Result	<u>Unit</u>	<u>Method</u>	Analysis Date
TPH 8015 DRO	< 0.40	mg/L	SW 8015B	2/2/01
Ref. Number: 168259	Site: MW-3		Date Sampled: January 19, 200	1 Time: 12:04 PM
<u>Parameter</u>	<u>Result</u>	<u>Unit</u>	<u>Method</u>	Analysis Date
TPH 8015 DRO	< 0.40	mg/L	SW 8015B	2/7/01 
Ref. Number: 168260	Site: MW-4		Date Sampled: January 19, 200	1 Time: 11:44 AM
Parameter	<u>Result</u>	<u>Unit</u>	<u>Method</u>	Analysis Date
TPH 8015 DRO	< 0.40	mg/L	SW 8015B	2/2/01

≡ **ENDYNE**, INC. 160 James Brown Drive

160 James Brown Drive Williston, Vermont 05495 (802) 879-4333 41500

Project Na	Pruso 4 1000	HNSOUPH W	Reporting	ng Add	Billing Address: CP-FFIA							
	to is.			-3 -	CP + CP	4-4-						
(Lab Use (	only) 1029		S Contact	Name			_ riioi	ις <i>π</i> .				
Ref# (Lab Use Only	Sample Identifi	Date/fime	No.	le Containers Type/Size	Field f	Results/Remarks	Analysis Required	Sample Preservation	Rush			
167256	DUPLILATE		Wall X		1264	3	10ml			9015 PA	44	
16825			1		1337				_,			
168258					1246						<del>                                     </del>	
16825-9	mw-3			<u> </u>	1204						<del>                                     </del>	
168260					1144	17	17			4	1 47	<u></u>
											<del> </del>	ļ <u> </u>
\				_							<del> </del>	<del> </del>
		·	<u> </u>	_		<u> </u>					<del> </del> -	
					ļ <u>.</u>	<u> </u>				-	<del>                                     </del>	<del> </del>
				<u> </u>		<u> </u>					<u> </u>	<u> </u>
Relinquished	by:	Date/Time	Received	by:			Date/Time	Receive	ed by:	<u></u>	Date/Ti	me
Now V-1	State Project: Yes	No X			Requested A	nalys	es					
		TKN	11	Total	Solids	16	Sulfate	21	1664 TPH/FOG	26	8270 PAH	
1 pH 2 Chlori		7 Total P	12	TSS		17	Coliform (Specify)	22	8015 GRO	27	PP13 Metals	
3 Ammo		Total Diss. P	13	TDS		18	COD	(23)	8015 DRO	28	RCRA8 Meta	ds
4 Nitrite	И	BOD	14	14 Turbidity		19	8021B	24	8260/8260B	29		
5 Nitrat	11	O Alkalinity	15		uctivity	20	8010/8020	25	8270 B/N or Acid	30		
31 Metal	(As Is, Total, Diss.) Ag, A	Al, As, B, Ba,	Be, Ca, Cd	Co,	Cr, Cu, Fe, H	g,K,	Mg, Mn, Mo, N	Va, Ni,	Pb, Sb, Se, Si, S	Sr, Ti, Tl,	V,Zn	
	(Specify: volatiles, sen					33						
34 Other	· ·· · · · · · · · · · · · · · · · · ·											



#### LABORATORY REPORT

#### **Laboratory Services**

160 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

Griffin International

PO Box 943

Williston, VT 05495

Attn:

PROJECT: Former St. Johns House/#100041751

ORDER ID: 11029

RECEIVE DATE: January 19, 2001

REPORT DATE: January 26, 2001

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody. Different groups of analyses may be reported under separate cover.

All samples were prepared and analyzed by requirements outlined in the referenced methods and within the specified holding times.

All instrumentation was calibrated with the appropriate frequency and verified by the requirements outlined in the referenced methods.

Blank contamination was not observed at levels affecting the analytical results.

Mus

Analytical method precision and accuracy was monitored by laboratory control standards which include matrix spike, duplicate and quality control analyses. These standards were determined to be within established laboratory method acceptance limits, unless otherwise noted.

Reviewed by,

Harry B. Locker, Ph.D. Laboratory Director

enclosures



#### **Laboratory Services**

160 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

#### LABORATORY REPORT

CLIENT: Griffin International

ORDER ID: 11029

PROJECT: Former St. Johns House/#100041751

DATE RECEIVED: January 19, 2001

REPORT DATE: January 26, 2001

SAMPLER: RD

	Site: MW-2 Ref. Number: 168258 Anal. Method: SW 8021B Date Sampled: 1/19/01 Time Sampled: 12:46 PM Analysis Date: 1/24/01 Analyst: 222		Site: MW-4 Ref. Number: 168260 Anal. Method: SW 8021B Date Sampled: 1/19/01 Time Sampled: 11:44 AM Analysis Date: 1/24/01 Analyst: 222	
Results ug/L	Parameter	Results ug/L	<u>Parameter</u>	Results ug/L
< 10.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0	MTBE Benzene Toluene Ethylbenzene Xylenes, Total 1,3,5 Trimethyl Benzene 1,2,4 Trimethyl Benzene Naphthalene UIP's	< 10.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0	MTBE Benzene Toluene Ethylbenzene Xylenes, Total 1,3,5 Trimethyl Benzene 1,2,4 Trimethyl Benzene Naphthalene UIP's	< 10.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0 99.%
98.%	Surrogate I  Site: MW-3 Ref. Number: 168259 Anal. Method: SW 8021B Date Sampled: 1/19/01 Time Sampled: 12:04 PM Analysis Date: 1/24/01 Analyst: 222	100.76	Surrogate 1	<i>551,16</i>
Results ug/L	<u>Parameter</u>	Results ug/L		
<10.0 <1.0 <1.0 <1.0 <1.0 <1.0 <1.0 <1.0	MTBE Benzene Toluene Ethylbenzene Xylenes, Total 1,3,5 Trimethyl Benzene 1,2,4 Trimethyl Benzene Naphthalene UIP's	< 10.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0 < 1.0		
	<1.0 <1.0 <1.0 <1.0 <1.0 <1.0 <1.0 <1.0	Anal. Method: SW 8021B Date Sampled: 1/19/01 Time Sampled: 12:46 PM Analysis Date: 1/24/01 Analyst: 222    Results ug/L	Anal. Method: SW 8021B   Date Sampled: 1/19/01   Time Sampled: 12:46 PM   Analysis Date: 1/24/01   Analyst: 222	Anal. Method: SW 8021B   Date Sampled: 1/19/01   Time Sampled: 1/19/01   Time Sampled: 1/24/01   Analysis Date: 1/0   Toluene   Ethylbenzene   C1.0   C1.

**≡ ENDYNE, INC.**160 James Brown Drive

160 James Brown Drive Williston, Vermont 05495 (802) 879-4333 41500

(802)	879-4333														4 1 <u>9</u>	
Project Nam	Project Name:  Formal Johns Dip I black Reporting Address:  Address:  Project Name:  Formal Johns Dip I black Reporting Address:  Address:  Sampler Name:  Sampler Name:															
Endyne Ord	er ID:		2-0	mpan	y:	GRIE	Sampler Name:									
(Lab Use Or	7 1 7 0 1 0 1 0 1 0 1 0 1 0 1 0 1 0 1 0										Pho	ne #:				1
(Lab Use Unity) 1029 -s Contact Name/Phone #: 20														_		
Ref # (Lab Use Only)	Sample Iden	tifica	ion N	Matrix	G R A B	C O M P	Date/fime	Sam No.	<del>-</del>	Containers Type/Size	Field l	Results/Remarks	Analysis Require	d	Sample Preservation	Rush
167256	DUPLICATE	<u>-</u>		6/2D	A		1264	3	Į.	40ml			803 II	5	44	
168257		<del></del>		1	4		1227	1	9	1		<del></del>	í			
	mw-1			+-	+		<del> </del>		十	<del>                                     </del>		<u> </u>				
168258	MW-2						1246	<del>   </del>		<del>-   -   -   -   -   -   -   -   -   -  </del>						
16825-9	<u>ww-3</u>	<u> </u>	+		1204		$\dashv$		<del></del>	<u></u>	4					
168260	ma-il				V	Ļ	1144	17	$\dashv$	47			77		7	
													<u> </u>			
															<u> </u>	
							******									
<b></b> -						1										
	<u> </u>		<u> </u>	<del> </del>	<u></u>	<u> </u>				Date/Time	Receive	d hur			Date/Tim	ne
Relinquished by			Date/Time	Rece	eived t	y:	<del></del>		1/	19/01	Receive	ar by.				
		2	-itiales		1	_	Faure	<u>//</u>	7	16/00			<u> </u>			<del> </del>
New York S	State Project: Yes	No	×			-	Requested A	nalys	ses							
	1	6	TKN		11	Total S	olids	16	Suli	fate	21	1664 TPH/FOG	2	26	8270 PAH	
1 pH 2 Chloride		7	Total P		12	TSS		17	ļ	liform (Specify)	22	8015 GRO		27	PP13 Metals	
3 Ammonia			—	13	TDS		18	co		<b>(</b> 23)	8015 DRO		28	RCRA8 Metals	s	
1 <del></del>		9	BOD		14 Turbidity		ity	19	╄	21B	24	8260/8260B	2	29		
4 Nitrite N 5 Nitrate N	<u> </u>		- 1	15	Condu	<u>.</u>	20	┿	10/8020	25	8270 B/N or Acid		30	-		
11 " 1							-	l)			<u> </u>	<u> L</u>		 7. N	√. Zn	
<u> </u>	As Is, Total, Diss.) Ag							Т	TAT	E, 14111, 1410, 14	ca, 1 11,	10,00,00,00,			,	
32 TCLP (	Specify: volatiles, s	emi-	volatiles, metal	ls, pestic	ides,	herbi	cides)	33				<del></del>				
1 24 00																



#### CHAIN-OF-CUSTODY-RECORD

160 James Brown Drive Williston, Vermont 05495 (802) 879-4333

41500

Proj	ect Name:	Billing Address:											
Endyne Order ID:  (Lab Use Only)  -O Company:  -I Contact Name/Phone #:													
Ref # (Lab Use Only) Sample Identification Matrix B P 1 1976							No.	Type/Size	Field	Results/Remarks	Analysis Required	Sample Preservation	Rush
	DIRLICATI	E.	M <sub>2</sub> O	1×	_	1264	3	7 40 ml	_		4012 PE	44	
	HAW-1				<u> </u>	1337							
	MW-3					1346							
	MM-3			4	-	1204					9	1	
	Wra-A	L		*	+	1144	1	17			49	7_	
				+			-			· · · · · · · · · · · · · · · · · · ·			
				-	1		-			· .			
ļ				+	-		<u> </u>					<u> </u>	
				+	<del> </del>		+						
					<u> </u>	<u> </u>		<u> </u>			1	Date/Tir	ne T
Reling	uished by:	)	Date/Time Re	ceived	by:	and the state of the state of	<u> [</u>	Date/Time	Received by: Date/Time				
 New	York State Project: Yes	N	·× ′	<i>,</i> #*	port	Requested A	nalys	ses					
<u> </u>	рН	6	TKN	11	Total S	olids	16	Sulfate	21	1664 TPH/FOG	26	8270 PAH	
l <del>⊢  </del>	Chloride	7	Total P	12	TSS		17	Coliform (Specify)	22	8015 GRO	27	PP13 Metals	
3	Ammonia N	8	Total Diss. P	13	3 TDS		18	COD	(23)	8015 DRO	28	RCRA8 Metal	s
4	Nitrite N	9	BOD	14	Turbidity		19	8021B	24	8260/8260B	29	·	
11 ~ 1	ll ~ [			15	Солди		20	8010/8020	25	8270 B/N or Acid	30		<del></del>
-	Metals (As Is, Total, Diss.) Ag					· · · · · · · · · · · · · · · · · · ·	g, K,	Mg, Mn, Mo, N	la, Ni,	Pb, Sb, Se, Si,	Sr, 11, 11,	v,∠n	
32	TCLP (Specify: volatiles, s	emi-	volatiles, metals, pesti	cides.	, herbio	rides)	33			····	· .	<del></del>	
34	Other												