

**Vermont Department of Environmental Conservation**

Watershed Management Division  
Springfield Regional Office  
100 Mineral Street, Suite 303  
Springfield, VT 05156  
www.watershedmanagement.vt.gov

*Agency of Natural Resources*

[phone] 802-885-8855  
[fax] 802-885-8890  
[cell] 802-345-3510

**AUTHORIZATION TO CONDUCT NEXT FLOOD MEASURES**

Pursuant to Section F of the Vermont Stream Alteration General Permit

Project Number: SA-05-023-2015 Jamaica Pikes Falls Rd Culvert 46      VTrans EA # THS-2015-305  
Applicant Name: Town of Jamaica      Contact: Paul Fraser  
Mailing Address: P.O. Box 173, 28 Town Office Rd, Jamaica, VT 0534      Phone: 802-874-4681  
Project Location: Pike Falls Rd TH 1 Culvert 46 over North Branch trib      Email: [frasercrew@aol.com](mailto:frasercrew@aol.com)

The Secretary of the Vermont Agency of Natural Resources (VT ANR) has determined that:

1. This project authorizes replacement of dual culverts damaged by T.S. Irene with a 3-sided 11" x 4' precast concrete culvert and associated wing walls and rip-rap stabilization over an un-named tributary to the North Branch of Ball Mountain Brook. The culvert invert to be stabilized with stone fill Type E1 as per Appendix M Stone Sizing.
2. The proposed activity is eligible for coverage under the VT ANR Stream Alteration General Permit – Next Flood Measures.
3. The proposed activity will meet the terms and conditions of Section F of the General Permit provided:
  - a) The project will be completed and approved as shown on the plans revised to 4/2/15, prepared by Holden Engineering, and approved by the Vermont Agency of Natural Resources as attached herein.
  - b) The project is proportional to the threat and conditioned to cease when the threat to life or to improved property has ended.
  - c) The project will not result in a threat to life, public health or safety.
  - d) The project will meet the standards detailed in subsection E.2.1 and E.2.2 of the General Permit.
  - e) The project will meet Stream Alteration Standards to the greatest extent possible.
  - f) A pre-construction meeting is held between the contractor, owner/applicant, and the ANR River Management Engineer.
  - g) The River Management Engineer is notified by phone or email when construction begins and when the project is complete.

If there are any changes in the project plan or deviation in construction from the plan, the Permittee must notify the River Management Engineer immediately.

If the project is constructed as you have described, as shown on the above referenced approved plans and according to the above conditions, there is no reason to expect any violation of Vermont Water Quality Standards.

Signed this 6<sup>th</sup> day of August, 2015  
David K. Mears, Commissioner  
Department of Environmental Conservation

This permit expires October 1, 2015.

by:   
\_\_\_\_\_  
Todd Menees, P.E., P.H., River Management Engineer

## **Streambed Stone Fill Design Guidance**

<b>Type</b>	<b>Velocity Range (fps)*</b>	<b>Embeddedness (in)</b>
E1	$V \leq 9$	18
E2	$9 < V \leq 11$	24
E3	$11 < V \leq 13$	36
E4	$13 < V \leq 15$	48

\*Maximum velocity should be based on a minimum 50-year design flow rate and calculated at the structure outlet.

### **Item xxx.xxx CY Streambed Stone Fill Specification**

Type E1. The longest dimension of the stone shall be at least 18 inches, and at least 50 percent of the volume of the stone in place shall have a least dimension of 12 inches, and at least 25 percent of the particles shall have a maximum dimension of 2 inches and be well graded material.

Type E2. The longest dimension of the stone shall be at least 24 inches, and at least 50 percent of the volume of the stone in place shall have a least dimension of 18 inches, and at least 25 percent of the particles shall have a maximum dimension of 2 inches and be well graded material.




Type E3. The longest dimension of the stone shall be at least 36 inches, and at least 50 percent of the volume of the stone in place shall have a least dimension of 24 inches, and at least 25 percent of the particles shall have a maximum dimension of 2 inches and be well graded material.

Type E4. The longest dimension of the stone shall be at least 48 inches, and at least 50 percent of the volume of the stone in place shall have a least dimension of 36 inches, and at least 25 percent of the particles shall have a maximum dimension of 2 inches and be well graded material.

#### Notes

- The streambed stone fill shall be hard, blasted, angular rock other than serpentine rock containing the fibrous variety chrysotile (asbestos). Similar sized river sediment is an acceptable alternative as is a mixture of angular material and river sediment.
- Stone placed inside of a closed structure shall be placed such that the structure is not damaged.
- Care shall be taken to limit segregation of the materials.
- Add sand borrow item as needed to seal the bed and prevent subsurface flow.
- There shall be no subsurface flow upon final inspection.

LEGEND	
---	EXISTING CONTOUR 1MR
---	EXISTING CONTOUR 1/4R
---	ALUMINUM GUARD RAIL
○	REBAR/IRON PIN FOUND
—○—	UTILITY POLE
⊕	SOIL BORING LOCATION
---	EDGE OF BROOK



**HOLDEN** TRANSPORTATION ENGINEERING

55 Old Smeeth Road - Unit #4  
 P.O. Box 480 Concord, NH 03302  
 (603) 225-6449  
 9 Constitution Drive  
 Bedford, NH 03110  
 (603) 472-2078

EXISTING CONDITIONS PLAN  
 PIKES FALLS ROAD CULVERT REPLACEMENT  
 JAMAICA, VT

DATE	REVISION DESCRIPTION	BY	CHK	BOOK	PAGE
XXXX					

Date: 12-01-14  
 Scale: 1" = 10'  
 Dr. By: RL Ck. By: WCP  
 Job No. 1470027  
 Sheet No. 2 of 16

**ROADWAY CONSTRUCTION NOTES**

1. ALL PROJECT MATERIALS AND CONSTRUCTION METHODS SHALL BE IN CONFORMANCE WITH THE VTRANS "2011 STANDARD SPECIFICATIONS FOR THE CONSTRUCTION BOOK" AND ALL APPENDIX THAT FOLLOW.

2. ROAD BUILDING PAVEMENT AND GRANULAR SUB-BASE COURSES FOR THE APPROACHES WILL BE AS FOLLOWS:

- 3.5 INCHES - BITUMINOUS CONCRETE PAVEMENT (ITEM 406.25)
- 1.5 INCHES OF WEARING COURSE PLUS 2 INCHES OF BINDER COURSE.
- 6 INCHES - SUB-BASE OF CRUSHED GRAVEL, FINE GRADED (ITEM 301.26)
- 18 INCHES - SUB-BASE OF GRAVEL (ITEM 301.15)

**DRAINAGE NOTES**

1. STATION 12+75 - LT. 20 FEET TO RT. 21 FEET  
CONSTRUCT 41 LF OF 15" RCP CLASS IV (ITEM 601.0811)  
SLOPE 0.03 FT/FT

2. CONSTRUCT STONE FILL TYPE II (ITEM 613.11) AND GEOTEXTILE UNDER STONE FILL (ITEM 649.31)  
AT THE PIPE OUTLET - CONSTRUCT STONE FILL FOR OUTLET PROTECTION ALONG THE SLOPE TO THE FOLLOWING DIMENSIONS: 5 FEET WIDE, 8 FEET LONG, AND 1.5 FEET DEEP.

NEAR THE PIPE INLET - CONSTRUCT STONE FILL TO STABILIZE THE 1:1 SLOPE AS SHOWN ON THE PLANS AND CROSS SECTION.

3. CONSTRUCT A TYPE II DELINEATOR WITH STEEL POST (PAY ITEM 676.10) TO MARK EACH END OF THE NEW 15" RCP PIPE.

**GUARDRAIL AND DELINEATOR NOTES**

1. ALL EXISTING GUARDRAILS WILL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR (PAY ITEM 621.80).

2. ALL NEW GUARDRAILS WILL BE STEEL BEAM GUARDRAIL, GALVANIZED ON STEEL POSTS (PAY ITEM 621.20).

STRAIGHT SECTIONS OF RAIL WILL BE CONSTRUCTED AT THE FOLLOWING LOCATIONS:

STATION 11+70, RT TO STATION 13+10, RT  
STATION 11+50, LT TO STATION 12+25, LT

CURVED SECTIONS OF RAIL WILL BE CONSTRUCTED AT THE FOLLOWING LOCATIONS:

STATION 11+58 RT TO STATION 11+70, RT RADIUS = 10', L = 18.75'

STATION 13+10 RT TO STATION 13+20, RT RADIUS = 10', L = 12.50'

STATION 11+34 LT TO STATION 11+50, LT RADIUS = 20', L = 18.75'

STATION 12+25 LT TO STATION 12+42, LT RADIUS = 20', L = 18.75'

CONSTRUCT ROUNDED "W" BEAM END SECTIONS AT THE ENDS OF ALL CURVED SECTIONS OF RAIL. PAYMENT WILL BE SUBSIDIARY TO ITEM 621.20.

3. STEEL BEAM GUARDRAIL DELINEATORS WILL BE PLACED ONTO EACH FIFTH POST (ITEM 621.218)

4. CONSTRUCT A TYPE II DELINEATOR WITH STEEL POST (PAY ITEM 676.10) AT THE FOLLOWING LOCATIONS TO MARK THE BEGINNING AND END OF STRAIGHT GUARDRAIL SECTIONS:

STATION 11+70, RT




STATION 13+10, RT

STATION 11+50, LT

STATION 12+25, LT

**PAVEMENT PAINT MARKING NOTES**

1. STATION 10+50 TO STATION 13+40  
CONSTRUCT 4 INCH DOUBLE YELLOW LINES ALONG THE ROAD CENTERLINE (PAY ITEM 646.21)



CURVE DATA				
CURVE	ARC LENGTH	RADIUS	DELTA	TANGENT
C1	220.50'	1250.00'	10°06'25"	110.54'
C2	41.08'	765.00'	3°04'38"	20.55'

SCALE: 1" = 10'



H-16  
WESLEY T. FROST  
233 LINCOLN ROAD  
LINCOLN, MA 01773-5100

H-19.1  
JEFFREY L. WOOD  
&  
APRIL C. WOOD  
12336 THUNDER BAY DRIVE  
INDIANAPOLIS, IN 46236

H-16  
WESLEY T. FROST  
233 LINCOLN ROAD  
LINCOLN, MA 01773-5100

**HOLDEN TRANSPORTATION ENGINEERING**

- ☐ 56 Old Suncook Road - Unit #4  
PO Box 480 Concord, N.H. 03302  
(603) 225-6449
- ☒ 9 Constitution Drive  
Bedford, N.H. 03110  
(603) 472-2078

**ROADWAY PLAN & TYPICAL SECTIONS  
PIKES FALLS ROAD CULVERT REPLACEMENT  
JAMAICA, VT**

DATE:	REVISION DESCRIPTION	DR. BY:	CHK. BY:	BOOK	PAGE
XXXX		XXXX	XXXX		

Date: 12-01-14  
Scale: 1" = 10'  
Dr. By: RL Ck. By: WCR  
Job No. 1470027  
Sheet No. 4 of 16

STA. 10 + 45  
LIMIT OF WORK

80.00' VC  
PM STA = 10+75  
PM ELEV = 1281.93  
A.O. = 5.14  
K = 11.68

BVCS: 10+45  
BVCE: 1284.89

EVCS: 11+05  
EVCE: 1280.51

STA. 11+05  
FIELD DRIVE, RT.



-4.2%

BVCS: 12+90  
BVCE: 1271.74

80.00' VC  
PM STA = 13+15  
PM ELEV = 1270.55  
A.O. = 2.81  
K = 17.81

EVCS: 13+40  
EVCE: 1270.07

STA. 13 + 40  
LIMIT OF WORK



DATUM: BENCH  
1285.00

1284.94  
1284.40  
1284.41

1281.93  
1282.32

1279.65  
1280.76

1277.64  
1279.56

1275.98  
1278.37

1274.75  
1277.19

1273.77  
1276.00

1272.94  
1274.82


1272.14  
1273.63

1271.31  
1272.45

1270.83  
1271.29

1270.35  
1270.42

1269.98



(\*) NOTE  
THE CLEAR WATERWAY OPENING WILL BE 11 FT.  
ABOVE THE CENTERLINE OF THE ROADWAY.  
THIS VIEW ALONG THE C.O. OF THE ROADWAY IS  
FOR INFORMATION ONLY. THE EXACT CLEARANCE  
DIMENSION IS 13 FT.

**HOLDEN** TRANSPORTATION  
ENGINEERING

56 Old Smeeth Road - Unit #4  
PO Box 480 Concord, NH 03302  
(603) 225-6449  
9 Constitution Drive  
Bedford, NH 03110  
(603) 472-2078





ROADWAY PROFILE  
PIKES FALLS ROAD CULVERT REPLACEMENT  
JAMAICA, VT

DATE	REVISION DESCRIPTION	BY	CHK	BOOK	PAGE
XXXX		XXXX	XXXX		

Date: 12-01-14  
Scale: H=10' V=2'  
Dr. By: RL Ck. By: WCR  
Job No. 1470027  
Sheet No. 5 of 16

CONSTRUCTION NOTES:

1. ALL SITE WORK SHALL BE IN CONFORMANCE WITH VERMONT AGENCY OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION," 2001 EDITION EXCEPT AS MODIFIED IN THE DRAWINGS, SPECIFICATIONS AND NOTES.
2. GROUNDWATER CONTROL MEASURES SHALL BE PERFORMED SO THAT THE EXCAVATION ACTIVITIES CAN BE CONSTRUCTED IN THE DRY AND LIMITING THE POTENTIAL FOR THE DISTURBANCE OF SUBGRADE SOILS.
3. EXCAVATION SIDESLOPES SHOULD BE NO STEEPER THAN THOSE ALLOWED BY OSHA, UNLESS BRACING OR FRENCH BOXES ARE UTILIZED.
4. FILL PLACED WITHIN CULVERT AREAS SHALL CONSIST OF GRANULAR BACKFILL FOR STRUCTURES (ITEM 204.30) MEETING THE GRADATION REQUIREMENTS OF 704.08.
5. PRECAST CONCRETE SHALL BE IN CONFORMANCE WITH SECTION 501, STRUCTURAL CONCRETE, AND SECTION 507, REINFORCING STEEL.
6. THE CAST IN PLACE CONCRETE FOOTING AND WINGWALL SHALL BE CLASS B (3500 PSY) AND THE REINFORCING STEEL BARS SHALL BE GRADE 60 EPOXY COATED.
7. THE PRECAST CONCRETE RIGID FRAME SHALL BE DESIGNED IN ACCORDANCE WITH ASHTO LRFD DESIGN SPECIFICATION 2012.



**HOLDEN** TRANSPORTATION ENGINEERING

56 Old South Road - Unit #1  
 P.O. Box 480 Concord, NH 03302  
 (603) 225-6449  
 9 Constitution Drive  
 Bedford, NH 03110  
 (603) 472-2078

DETAILS - FOOTINGS, ABUTMENTS & WINGWALLS  
 PIKES FALLS ROAD CULVERT REPLACEMENT  
 JAMAICA, VT

REVISION	DATE	DESCRIPTION	BY	CHK	BOOK	PAGE
XXXX	XXXX					

Date: 12-01-14  
 Scale: AS SHOWN  
 Dr. By: RL Ck. By: WCR  
 Job No. 1470027  
 Sheet No. 10 of 16

## HAZARDOUS MATERIALS PLAN

### INVENTORY FOR POLLUTION PREVENTION PLAN

- THE MATERIALS OR SUBSTANCES LISTED BELOW ARE EXPECTED TO BE PRESENT ON-SITE DURING CONSTRUCTION
- CONCRETE
  - PETROLEUM BASED PRODUCTS
  - PAINTS (EMULSION, OIL, LATEX)
  - METAL
  - ASPHALT
  - TARMAC
  - SHINGLES
  - MASONRY BLOCK
  - ASPHALT

### SPILL PREVENTION PLAN NOTES:

#### MATERIAL MANAGEMENT PRACTICES

THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT WILL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES TO STORM WATER RUNOFF

#### GOOD HOUSEKEEPING

1. AN EFFORT WILL BE MADE TO STORE ONLY ENOUGH PRODUCT DURING THE CONSTRUCTION PROJECT
2. ALL MATERIALS STORED ON-SITE WILL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER ENCLOSURE
3. PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S LABEL
4. SUBSTANCES WILL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER
5. WHENEVER POSSIBLE, ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE CONTAINER
6. MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE FOLLOWED
7. THE SITE SUPERINTENDENT WILL INSPECT DAILY TO ENSURE PROPER USE AND DISPOSAL OF MATERIALS ON-SITE.

#### HAZARDOUS PRODUCTS

THESE PRODUCTS ARE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS.

1. PRODUCTS WILL BE KEPT IN ORIGINAL CONTAINER UNLESS THEY ARE NOT RESEALABLE.
2. ORIGINAL LABEL AND MATERIAL SAFETY DATA WILL BE RETAINED; THEY CONTAIN IMPORTANT PRODUCT INFORMATION.
3. IF ORIGINAL PRODUCT MUST BE DISPOSED OF, MANUFACTURER'S OR LOCAL AND STATE RECOMMENDED METHODS FOR PROPER DISPOSAL WILL BE FOLLOWED.

#### PRODUCT SPECIFIC PRACTICES

##### PETROLEUM PRODUCTS

1. ALL ON-SITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE
2. ALL VEHICLE REFUELING, OILING AND / OR GREASING SHALL BE CONFINED TO A DESIGNATED AREA OF THE PROJECT. ALL SPILLS SHALL BE IMMEDIATELY CLEANED UP AND REPORTED TO THE SUPERVISOR. RESTORATION OPERATIONS SHALL BE PERFORMED AS NECESSARY.
3. SHOULD ANY FUEL, HYDRAULIC OIL, OR ENGINE OIL SPILL OCCUR:
  - a) THE PLASTIC ON THE LOWER SIDE OF THE PAO SHALL BE STAYELED UP
  - b) ANY CONTAMINATED SOILS SHALL BE HALLED OFF-SITE AND DISPOSED OF BY AND THROUGH A STATE APPROVED HAZARDOUS MATERIAL DISPOSAL CONTRACTOR.
4. PLASTIC AREAS EXPOSED TO SUNLIGHT SHOULD BE CHECKED EVERY TWO WEEKS TO ENSURE THAT THE PLASTIC IS PROPERLY PLACED. THE PAO SHALL BE UNDERLAIN WITH NEW PLASTIC.

##### HAZARDOUS MATERIALS

5. IN THE EVENT OF A LARGE SPILL (25 GALLONS OR MORE), CONTACT THE STATE OF VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION (DEC) WASTE MANAGEMENT DIVISION 800-641-5005 24-HOUR REPORTING
6. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED.
7. ASPHALT PRODUCTS USED ON-SITE WILL BE APPLIED AND STORED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS

##### FERTILIZERS

1. FERTILIZERS USED WILL BE APPLIED ONLY IN THE MINIMUM AMOUNTS RECOMMENDED BY THE MANUFACTURER
2. ONCE APPLIED, FERTILIZER WILL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE TO STORM WATER
3. STORAGE WILL BE IN A COVERED SHED
4. THE CONTENTS OF PARTIALLY USED BAGS WILL BE TRANSFERRED TO SEALABLE BAGS.

##### PAINTS

1. ALL CONTAINERS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE.
2. EXCESS PAINT AND CLEANING MATERIALS WILL NOT BE DISCHARGED TO THE STORM SEWER SYSTEM BUT WILL BE PROPERLY DISPOSED OF ACCORDING TO MANUFACTURER'S INSTRUCTIONS OR STATE AND LOCAL REGULATIONS.

##### CONCRETE TRUCKS

1. CONCRETE TRUCKS WILL NOT BE ALLOWED TO WASH OUT OR DISCHARGE SURPLUS CONCRETE OR BRIM WASH WATER WITHIN ANY CRITICAL BUFFER OR PROTECTION ZONE.

#### SPILL PREVENTION PLAN NOTES:

IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN, THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP:

1. MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.
2. MATERIAL AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREA
3. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY
4. SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY
5. THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM OCCURRING AGAIN AND IT WILL BE ADJUSTED IF ADDITIONAL HAZARDOUS MATERIALS ARE BROUGHT ON-SITE
6. THE ON-SITE SUPERVISOR WILL APPOINT A PERSON RESPONSIBLE FOR DAILY AND WEEKLY INSPECTIONS AND REPORTS.


## NON STORM WATER DISCHARGES

THE FOLLOWING NON STORM DISCHARGES WILL ACCRUE FROM THE SITE DURING CONSTRUCTION AND WILL BE PROPERLY TREATED PRIOR TO DISCHARGE.

1. WATER FROM WATER LINE FLUSHING
2. PAVEMENT WASH WATERS (WHERE NO SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE OCCURRED).
3. UNCONTAMINATED GROUNDWATER FROM DEWATERING EXCAVATION


## WASTE DISPOSAL

1. ALL WASTE MATERIALS WILL BE COLLECTED AND STORED IN A METAL DUMPSTER SUPPLIED BY THE LICENSED SITE WASTE MANAGEMENT COMPANY. THE DUMPSTER WILL BE LOCATED AND STATE SOLID WASTE MANAGEMENT REGULATIONS.
2. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE DUMPSTER
3. THE DUMPSTER WILL BE EMPTIED WHEN IT HAS REACHED ITS DESIGN CAPACITY.
4. NO CONSTRUCTION WASTE MATERIALS WILL BE BURIED ON-SITE.
5. ALL HAZARDOUS WASTE MATERIALS WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATIONS OR BY THE MANUFACTURER.
6. PORTABLE SANITARY FACILITIES WILL BE OPERATED BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR AS REQUIRED BY LOCAL AND STATE REGULATIONS. THESE FACILITIES WILL BE CLEANED AS NECESSARY TO MAINTAIN A CLEAN AND SANITARY FACILITY.
7. ALL PERSONNEL WILL BE INSTRUCTED REGARDING THE CORRECT PROCEDURE FOR WASTE DISPOSAL. NOTICES STATING THESE PROCEDURES MUST BE POSTED ON THE SITE
8. THE INDIVIDUAL APPOINTED BY THE SITE CONTRACTOR OR OWNER TO DO SITE INSPECTIONS SHALL BE RESPONSIBLE FOR SEEING THAT THESE PROCEDURES ARE FOLLOWED.




## STRAW OR HAY BALE AND FILTER BARRIER

- 1.) BARRIER TO REMAIN UNTIL GRASS IS GROWING IN ALL SEEDING AREAS.
- 2.) PROVIDE HAY BALES ON ALL SIDES OF CATCH BASIN, FROM WHICH FLOW CAN APPROACH CATCH BASIN.




#### CONSTRUCTION SPECIFICATIONS:

- 1.) ADJACENT BALES
- 2.) EACH BALE SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF 4"
- 3.) BALES SHALL BE SECURELY ANCHORED IN PLACE BY STAKES OR REBAR DRIVEN THROUGH PREVIOUS LAY BALE TO FORM BALE TOGETHER.
- 4.) ROADWAY AREAS STONE STUMP GROUNDS OR STONE TO BE PLACED TO A MINIMUM OF 1/2 THE BALE HEIGHT
- 5.) INSPECTION SHALL BE FREQUENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
- 6.) BALES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFULNESS SO AS NOT TO BLOCK OR WEDGE STORM FLOW OR DRAINAGE.




- 6 mil. POLYETHYLENE SHEET (2' EXPOSED ON DOWNWARD SLOPE AND 4' EXPOSED ON UPWARD SLOPE) FOLDED OVER SLOPE AND SECURED IN THE CASE OF A HAZARDOUS MATERIAL SPILL



## TEMPORARY VEHICLE MAINTENANCE PAD


NOT TO SCALE



## TEMPORARY STABILIZED CONSTRUCTION ENTRANCE

NOT TO SCALE


1. STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 2 TO 4 INCH STONE, RECOMMEND STONE OR RECYCLED CONCRETE EQUIVALENT.
2. THE THICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES
3. GEOTEXTILE FILTER CLOTH SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING THE STONE.
4. ALL SURFACE WATER THAT IS FLOWING TO OR DIVERGED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PREP BEHIND THE ENTRANCE.
5. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS OF WAY.
6. WHEELS SHALL BE CLEANED TO REMOVE MUD PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE WHEN DEBRIS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.



## TEMPORARY FABRIC SILTATION FENCE

NOT TO SCALE

1. FENCE CLOTH TO BE FASTENED SECURELY TO WOODEN WIRE FENCE WITH TIES SPACES EVERY 24"
2. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6 INCHES, FOLDED AND STAPLED.
3. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.



## SPACING BETWEEN STRUCTURES

NOT TO SCALE



## TEMPORARY & PERMANENT ROCK DAM DETAIL

NOT TO SCALE

# HOLDEN ENGINEERING

TRANSPORTATION  
9 Constitution Drive  
Bedford, NH 03110  
(603) 472-2008

# EROSION CONTROL DETAILS

PIKES FALLS ROAD CULVERT REPLACEMENT  
JAMAICA, VT

DATE: XXXX  
REVISION DESCRIPTION: XXXX  
BOOK PAGE: XXXX  
Date: 12-01-14  
Scale: N.T.S.  
Dr. By: R.L. Ck. By: WCP  
Job No. 1470027  
Sheet No. 11 of 16